Arboricultural Report
BS5837:2012 Trees in Relation to
Design, Demolition and Construction
- Recommendations

Blentarn Cadnant Park Conwy LL32 8PE

Document Ref: CPC_0924_5837

Date: 27/09/2024

Prepared By: Matt Bardsley

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Cont	ents	Page No.
Prea:	mble ations	4 5
	Section 1 Tree Survey	3
1.1	Site description	6
1.2	Tree survey	7
1.3	Tree categorisations explained	8
1.4	Site visit parameters	9
1.5	Constraints posed by existing trees	9
1.6	Associated Information	9
1.7	Soil assessment	10
	Section 2 Arboricultural Impact Assessment	
2.1	Development Proposal	11
2.2	Predicted Impact of the Proposal	11
2.3	Trees proposed for Removal	12
2.4	Trees to be retained with disturbance of RPAs	12
2.5	Visual impacts of the tree works proposed – summary	13
2.6	Mitigation planting	14
2.7	Protection of retained trees	14
2.8	Infrastructure and Utility Works	14
2.9	Works within Root Protection Areas	15
2.10	Working corridors	15
2.11	Long term tree retention and social proximity	15
	Section 3 Arboricultural Method Statement	
3.1	Arboricultural Supervision requirements	17
3.2	Protective fencing discussion	17
3.3	Works flow sequence	17
3.4	Quality of tree work	18
3.5	Site supervision during construction	18
3.6	Landscaping	18
3.7	Generic tree protection measures	19
3.8	Notes for the use of working corridors	19
Secti	on 4: Appendices	
	Appendix 1 – Definitions / glossary of terms	20
	Appendix 2 - Tree Survey Data Sheets	22
	Appendix 3 – BS5837:2012 Cascade Chart for tree categorisation	30

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Appendix 4 – Protective fencing		31										
Appendix 5 – RPA signs		33										
Appendix 6 - Working Corridor - Scaffolding or light foot traffic within the RPA												
Appendix 7 – Vegetation Plan		37										
Appendix 8 – Tree Location Plan		38										
Appendix 9 – Tree Constraints Plan		39										
Appendix 10 – Tree Protection Plan		40										
Appendix 11 – Site images		41										
Credentials of the arboriculturalist	46											
Bibliography	47											

End of Document	48

Ref.	Revision date	Type of revision	Prepared/amended by
CPC_0924_5837	27/09/2024	First issue	Matt Bardsley
CPC_0924_5837	8/10/2024	Tree locations amended	Matt Bardsley

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Preamble

BS5837 is the British Standard for the protection and retention of trees on a proposed development site and is titled 5837:2012 "Trees in relation to design, demolition and construction – Recommendations".

BS5837 provides recommendations on how trees should be assessed and which of those trees should be protected during development together with how that protection will be achieved.

A BS5837 report will serve two primary purposes -

- 1) To help the Local Planning Authority assess the likely impacts of the development on the trees growing on and around the site and how any proposed changes may affect the character of the area.
- 2) To aid the developer in knowing which trees should be considered as a constraint and how the development can co-exist with those trees.

With the above in mind, this report has been commissioned for the purpose of providing an assessment of trees growing at Blentarn, Cadnant Park, Conwy and has been prepared in accordance with the guidance specified in BS5837:2012 *Trees in Relation to Design, Demolition and Construction – Recommendations.*

The following report consists of three main components as prescribed in the British Standard and as detailed below.

- 1. The Tree Survey records all the relevant information required when assessing trees for retention, including any impacts the proposed development may have. In accordance with BS5837 the Tree Survey also provides details of those trees adjacent to the site which may be affected, or which are considered as growing within influencing distance of the development. However, to a certain degree information relating to neighbouring trees may be dependent on access. This section should be read in conjunction with the Tree Survey Data Sheets (Appendix 2) and the Tree Location Plan, (Appendix 8), which identifies the location of all the trees which need to be considered.
- 2. The **Arboricultural Impact Assessment** provides an insight into what impact any proposed development may have on the trees within and immediately adjacent to the site. The Arboricultural Impact Assessment should be read in conjunction with the **Tree Constraints Plan**, (Appendix 9). The Tree Constraints Plan shows each tree's crown spread colour coded to its retention category with the root protection area identified in grey.
- 3. The **Arboricultural Method Statement** provides details as to how the trees proposed for retention will be protected and managed for the duration of the development. This part of the document should be read in conjunction with the **Tree Protection Plan**,

Carlo Carlo (A)

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

which clearly identifies the location of the required protective fencing and its construction together with any special construction techniques required as per the recommendations of BS5837.

The **Tree Survey**, **Impact Assessment** and **Method Statement** combine to provide the developer and the Local Planning Authority with the information required to assess the trees in their current context and the future development proposal.

Limitations

All tree inspections were made from ground level only and cannot be considered as a tree safety survey. However, where obvious defects have been seen they have been noted.

Plans within this report are based on those supplied by the client. Greenspaces Tree & Landscape Consultants Ltd take no responsibility for the accuracy of the supplied plans.

Where ivy is too dense to easily remove, measurements have been made over it. In any instances where this is the case, it is clearly stated in the Tree Data Tables.

The findings and recommendations of this report are valid for a period of 18 months from its receipt by the client.

This report and any associated documentation, including plans, remains the property of Greenspaces Tree & Landscape Consultants Ltd until paid for in full.

Where plans have been cropped to fit the report, they may not be to scale.

The plans within this report should be printed in colour if hard copies are required.

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk Web:www.greenspacetrees.co.uk

Penmaen Isa

Section 1 Tree Survey

1.1 Site description

Blentarn is situated on the west side of Cadnant Park, Conwy and is accessed via a residential driveway located between 34A and 36A Cadnant Park (the site is circled with the continuous yellow line on the Google Maps image below).

The area proposed for development comprises grassed lawn with generic shrub beds enclosed on three sides by intermittently planted common and ornamental tree species, and hedges. An area of native woodland occupies the north of the site.

The trees vary in size and age from large 20m+ mature examples in the woodland to smaller, semi-mature trees of 2-3m in height in the maintained garden area. Shrub beds have been well maintained and comprise of common generic species at various points around the gardens.

Views into the site are limited to those properties along Cadnant Park which neighbour it to the east whilst a tall cypress hedge prevents views into the site from those properties to the south.



Image from Google Maps

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

The site has been well landscaped historically with a mix of both ornamental and native trees together with the previously mentioned shrub beds separating various elements and terraces of the garden. *Appendix 7 provides the locations of these shrub beds and hedges as a site plan.

*BS5837, Sect. 4, sub-sect. 4.4.2.7 ".... In the case of regularly maintained domestic hedges and the majority of shrub masses, it will normally be sufficient to record their height and species on the tree survey plan <u>or</u> note these in the schedule..."

1.2 Tree Survey

All trees with a diameter of 75mm or greater growing on the site, and those which are growing within influencing distance of the proposed development, have been recorded using the guidance specified in Annexe C of BS5837.

Diameters and sizes have been measured using a purpose designed diameter tape or callipers, surveyor's tapes and, where appropriate, a laser measure. Where accurate measurements have not been possible, an approximate size has been given. Trees with estimated dimensions are given the abbreviation "Est." or the fact that they have been estimated has been included in the comments section of the Tree Data Tables.

A total of forty-two individually growing trees and two groups have been measured, categorised and recorded for the purpose of this report (refer to Appendix 2). The location of other vegetation such as shrub beds and hedges has been provided on the plan in Appendix 7.

Crown spread and height has been provided to the nearest full metre with diameters given millimetres. However, where access has not been possible measurements may have been estimated.

The schedule containing information for those trees on and around the site has been provided in Appendix 2 with tree locations plotted on the enclosed Tree Location Plan provided in Appendix 8.

The Tree Survey Data Sheets provided in Appendix 2 identifies the following information.

Tree No. The unique number given for each tree and used to specify trees throughout this document. The number relates to a small, circular metal tag attached to the tree at 1.5m above ground level which is used to aid identification. These numbers can also be seen on the associated plans within this report. However, the plans not only show the number but also the retention category, for example tree 7762 has been categorised as a category A tree and therefore the number on the plan is 7762A (see the following sect. 1.3 for further details on categorisation).

Species Common name given, for example oak, ash, sycamore etc., with botanical names provided where further clarification is needed.

Age Class Y – Young (small, newly planted and in aid of support such as stakes and ties), **IMM** – Immature (less than a third of the mature tree's dimensions), **SM** - Semi-mature (established and over a third of the mature tree's dimensions), **EM** - Early mature (over two

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Jenje of the col

thirds of the mature tree's dimensions), \mathbf{M} – Mature (has reached its full growth potential), \mathbf{OM} – Over mature (likely in decline or close to it).

Height measured to the nearest metre.

Crown Spread measured at the four cardinal points. Off-site trees may only have the on-site spread measured with the remaining spread being estimated.

First Branch the height of the first branch from ground level (GL) and its direction, for example 3N would signify a branch at approximately 3m above ground level on the tree's north side.

Physiological condition a brief, general description of the tree's health/vigour described as Poor, Fair or Good. Elaborated on, where necessary, in the "Comments" box.

Structural condition a brief, general description of the tree's structural condition described as Poor, Fair or Good. Elaborated on, where necessary, in the "Comments" box.

Est. Remaining Contribution as per Appendix 1; <10yrs, 10-20yrs, 20-40years, >40yrs

Comments A brief summary of any issues or benefits identified.

Category Refers to the retention category: A, B, C or U as explained further in Sect. 1.3 below and Appendix 3.

Recommendations may include works essential for the proposed development or works necessary to retain or improve a tree's health/vigour or safe useful life expectancy.

D.B.H. Diameter at breast height measured in millimetres at 1.5m above ground level (BS5837, sect. 4, sub-sect. 4.6.1)

RPA Root Protection Area given as a radius for the protection of roots around the retained tree and shown on the associated Tree Protection Plan. The calculated volumes and radius have been provided in the Tree Data Tables and follow the formula described in para. 4.6 of BS5837.

1.3 Tree categorisations explained

Trees have been categorised as per the recommendations described in Table 1 of BS5837:2012. A copy of Table 1 has been included in this report as Appendix 3.

Categories identified in Table 1 of BS5837 can be summarised as follows:

Category A (colour coded green) Trees in good physiological and structural condition which provide a substantial contribution in terms of landscape, cultural or arboricultural value and with an estimated life expectancy which exceeds 40 years.

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Gally - Die mi

Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk Web:www.greenspacetrees.co.uk

Penmaen Isa

Category B (colour coded blue) Trees of a moderate quality and value and which have an estimated life expectancy which exceeds 20 years.

Category C (colour coded grey) Trees of a moderately low quality and/or value with a life expectancy which exceeds 10 years or trees with a diameter of 150mm or less.

Category U (colour coded red) Trees of a size which can be easily mitigated or trees which are in poor physiological and/or structural condition and/or with a life expectancy of 10 years or less.

In addition to the above, BS5837 provides sub-categories to give each tree a context for its value as follows:

- 1. Mainly arboricultural
- 2. Mainly landscape
- 3. Mainly cultural (including conservation benefits)

There is a total of forty-two individually recorded trees and two groups on, or within influencing distance, of the area proposed for development. These have been categorised in accordance with BS5837 (see Appendix 3) as below.

Category A	Category B	Category C	Category U
3	11	13	17

1.4 Site visit parameters

The site was visited on 21st September 2024 with the weather conditions being clear and bright with sunshine. The weather did not impair visibility, and the all the trees could be clearly seen unless otherwise stated in the tree data tables.

Trees seen to be growing within influencing distance of the development have, in accordance with BS5837:2012, been included in the survey and report.

1.5 Constraints posed by existing trees

Development can cause both long and short-term impacts to tree health and stability, particularly through inadequate protection of Root Protection Areas. However, below ground tree constraints may alter if root growth has been inhibited, for example, due to topography or drainage (BS5837 Sect. 4, Sub-Sect 4.6.3.)

The associated Tree Protection Plan provides an illustrative guide to the below ground constraints in terms root protection areas and the above ground crown spreads. The supporting Tree Protection Plan identifies the colour coded retention category of each tree as per para. 1.3 with the crown spreads colour coded to the appropriate retention category.

1.6 Associated information

Plans showing the existing and a draft proposed site layout were provided by the client prior to my site visit.

Galley - Domes

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

The above mentioned plans have been checked on site and used as the base plan for those in the attached appendices. Greenspaces Tree and Landscape Consultants take no responsibility if the information on the received and reproduced plans is inaccurate.

1.7 Soil assessment

In accordance with BS5837 sect. 4.3, a soil assessment should be carried out by a competent person. Such an assessment is usually undertaken as part of the initial planning of a landscape scheme. With this in mind only a desktop study has been undertaken in terms of this report.

For the purpose of conforming to the British Standard a brief soil assessment can be found below (information obtained from Landis {www.landis.org.uk})

Soilscape 6: Freely draining slightly acid loamy soils

Texture: Loamy

Drainage: Freely draining

Fertility: Low Carbon: Low

Drains to: Local groundwaters and rivers

The soil type described above is not thought to be an issue in terms of shrinkable clay subsidence and would be suitable for planting a range of trees and shrubs in gardens and landscaped areas.

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk Web:www.greenspacetrees.co.uk

Penmaen Isa

Section 2 Arboricultural Impact Assessment (AIE)

2.1 Development proposal

The proposal is to demolish the existing dwelling and introduce thirteen new houses, eleven detached and two semi-detached.

A row of four houses is proposed along the north of the site, adjacent to the existing woodland, two houses are located on the west boundary, four on the south and three on the east.

The plan below shows the general arrangement with plot numbers added to aid further descriptions throughout this report.



2.2 Predicted impact of the proposal

The layout necessitates the removal of all the ornamental trees, shrubs and hedges currently growing in the garden area.

Storm damaged and lower quality trees in the woodland at the northeast of the site are also proposed for removal. However, the higher quality woodland area remains intact.

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

2.3 Trees proposed for removal

The proposal necessitates the removal of a total of thirteen individually growing trees and two groups with a further fifteen trees and one group proposed for removal regardless of development.

All the trees proposed for removal are shown below.

Category A trees proposed for removal - none

Category B trees proposed for removal – five individually growing trees and one group


Category C trees proposed for removal – eight individually growing trees are proposed for removal

Category U – fourteen individually growing trees and one group are proposed for removal

2.4 Trees to be retained with disturbance of root protection areas

Minor incursion into the root protection area of trees 7760 and 7768 is required as below (shaded red).

The grey blocked out areas on the plan extract denote balconies raised well above the ground and supported by beams of up to 200mm diameter. The location of the beams are identified by the red dots. Should consent be granted the beams will have to be hand dug to minimise disturbance.



Incursions into root protection areas are quantified on the following page.

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Tree No.	RPA (M²)	Volume Affected (M²)	% Affected	Can the tree be successfully retained
7760	185.3m²	3.49m²	1.9%	Yes – the volume is well below that recommended in BS5837*
7768	197m²	4.56m²	2.3%	Yes – the volume is well below that recommended in BS5837*

^{*}BS5837:2012 para 7.4.2 Design recommendations, sub-para. 7.4.2.3 states that "New permanent hard surfacing should not exceed 20% of any existing unsurfaced ground" whilst para. 5.3, sub-para. 5.3.1 states that "...if operations within the RPA are proposed, the project arboriculturalist should; a) demonstrate that the tree9s) can remain viable and that the areas lost to encroachment can be compensated for elsewhere, contiguous with its RPA..."

In my opinion, due to the small volumes involved, the root protection areas of trees 7760 and 7768 can be off set into the woodland without having any negative effects on the trees.

A working corridor of 1m is also proposed. This will be achieved with a raised wooden walkway to protect the root protection areas as described in Appendix 6.

2.5 Visual impacts of the tree works proposed – summary

Tree No.	Species	Category	Description of loss	Mitigation measures
7746	Cypress	U	Declining tree in a prominent location at the entrance to the site	
7748 & 7749	Cherry	С	Only visible from within the site, not thought to be a loss to wider landscape	
7752 - 7757	Cherry Sycamore & Elm	U	Only visible from within the site, not thought to be a loss to wider landscape	Off-site planting
7769	Sycamore	U	Only visible from within the site, not thought to be a loss to wider landscape	proposed. Details of
7773 7775 7777 7778 7779 7790 7791 7794	Cherry Whitebeam Sycamore Laburnum Laburnum Cypress Willow Cypress	U	Visible from some houses on Cadnant Park, otherwise visible from within the site only	species, sizes and layout to be provided by applicant.
			Continued the following page	

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk Web:www.greenspacetrees.co.uk

Penmaen Isa

Tree No.	Species	Category	Description of loss	Mitigation measures
7772 7774	Sycamore Western			
1774	red cedar			
7780	Beech	С	Visible from some houses on Cadnant Park,	
7782	Whitebeam		otherwise visible from within the site only	
7783	Magnolia			
7784	Willow			
7785 7792	Apple			Off site planting
1192	Cherry			Off-site planting proposed.
				Details of
7771	Yew	В	Ornamental, well-trimmed small tree only	species, sizes
			visible from within the site, no loss to the	and layout to
			wider landscape	be provided by
7776	Beech			applicant.
7787	Western red cedar	В	Visible from some houses on Cadnant Park	
7788	Western	Ь	and from possible distant views	
1,700	red cedar		and nom possible distant views	
7789	Western			
	red cedar			
7793	Cherry			
	group			

2.6 Mitigation planting

The layout leaves little room for mitigation planting beyond adding trees in the woodland block to the north. However, mitigation planting is proposed on a site close by. Details of which will be provided with the application.

2.7 Protection of retained trees

Regardless of a tree's statutory protective status, if it is identified and agreed for retention there is a requirement for its physical protection as described in BS5837. The Arboricultural Method Statement provided in section 3 of this report gives detailed recommendations of how this protection will be achieved. Provided these recommendations are followed the development is not considered to have a detrimental effect on those trees identified for retention.

2.8 Infrastructure and utility works

All infrastructure and utility works should be carried out in accordance with the guidance provided in the document *National Joint Utilities Guides 4* and, where prescribed by the Local Planning Authority, works will be carried out under the supervision of a qualified and experienced arboriculturist. However, service runs through root protection areas should be avoided. If this is not possible then any incursion of the root protection area must be hand dug and agreed with the Local Planning Authority prior to any excavation works. This

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

agreement should be in writing and may require an additional method statement from those undertaking the works.

2.9 Works within Root Protection Areas

As can be seen in para. 2.4, incursion into the root protection area of trees 7760 & 7768 is minimal, (less than 3%), and is not likely to influence the trees physiological condition or their safe useful life expectancies.

2.10 Working corridors

Working corridors will be required in the areas shaded green on the plan extract below. The working corridors are to be 1m in width and follow the construction method as described in Appendix 6 and the general notes in para. 3.9




Access for the delivery of materials will be by the existing access from Cadnant Park.

2.11 Long term tree retention and social proximity

The development is for residential use with the northern most plots being sited next to mature woodland. This will have an effect in terms of seasonal nuisance, particularly leaf fall, and percieved threat.

Loss of sunlight during the summer is not thought to be a significant consideration as shown on the plan extract left which shows shading potential at mid-day, mid-summer.



Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

A tree safety assessment should be undertaken and any recommended works carried out before the properties are occupied. The occupiers should be made aware that it will be there duty going forward to have the trees inspected as per their legal obligations.

Potential leaf fall issues should be clearly explained to purchases and composting of the fallen leaves within the woodland encouraged.

Provided potential occupiers are aware of the above then proximuity to the trees should not result in significant future conflicts.

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Section 3 Arboricultural Method Statement (AMS)

This section should be read in conjunction with the associated Tree Protection Plan both of which should be kept on site for reference during all stages of the development.

3.1 Arboricultural supervision requirments

Pre-commencment meetings should identify the need, or otherwise, for arboricultural supervision and at which stages arboricultural imput may be required.

Digging the holes for the pillars to support the balconies as identified in para. 2.4 should be done under arboricultural supervision so that any roots encountered can be pruned correctly.

Arboricultural supervision may also be requested by the Local Planning Authority or required in order to comply with a Condition relating to a Planning Permission.

3.2 Protective fencing discussion

Refer to drawings shown in Appendix 4 and as provided from BS5837:2012 for protective fence design and ground protection.

The suggested location of the protective fencing is given in Appendices 10 "Tree Protection Plan".

The protective fencing should be erected prior to any construction or demolition stages and must remain in place for the duration of the development in accordance with any Conditions imposed by the Local Planning Authority.

The fencing is intended as a precaution to prevent accidental damage to the rooting area of retained trees. However, no materials should be stored inside the protective area and no waste run off, for example from the cleaning of equipment, should be allowed to enter the root protection areas.

It is recommended that signs are fixed to the protective fencing as shown in Appendix 5.

3.3 Works sequence

Order of Work flow	Work required
1	Pre-commencement meetings if required
2	Carry out any prescribed tree works
3	Install tree protection in accordance with Appendix 10
4	Carry out any required demolition if required
5	Introduce site facilities, car parking etc.
6	Construction starts
7	Introduction of landscaping or mitigation planting outside of the
	construction area
8	Construction completed

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

9	Remove protective fencing											
10	Landscape within construction area if required											
	Development complete											

3.4 Quality of tree work

All tree work should be in accordance with the British Standard for tree work "BS3998:2010 Tree work – Recommendations."

Your tree contractor should be familiar with the Standard and understand its contents evidenced by prior works of a similar nature.

Care should be taken that compaction does not occur through the use of heavy machinery around trees and wood chip should not be stored or left within the root protection area of trees.

In the interests of the environment, tree stumps should be ground out with a stump grinder or dug out rather than poisoned. Stump grinding is less impactful to the environment than digging stumps out.

Severing of ivy should be with hand tools such as pruning saws or secateurs and not chainsaws or hedge cutters.

Bats are European protected species, and great care is needed not to disturb them. Your chosen contractor should be familiar with the signs and evidence of bat activity and seek advice where needed. Similarly, your contractor needs to understand legislation in terms of nesting birds and work accordingly.

3.5 Site supervision during construction

The site manager should have a copy of this report and be aware of which trees are to be retained and protected from the earliest stages.

The site manager should brief those working close to trees or undertaking activities which may accidentally affect them so as to avoid any incidents of damage either above or below ground. Should damage occur then the Local Planning Authority should be contacted and made aware of the situation.

3.6 Landscaping

Landscaping should be carried out when the tree protection is removed and should not involve any digging other than by hand in the root protection area. Any roots encountered should not be severed or damaged.

Many of a tree's feeder roots can be seen in the first 300mm of soil and for this reason rotovators and similar equipment must not be used within the root protection areas.

Where possible the soil should not be altered within root protection areas with fertilisers etc. and care should be taken that compaction does not occur as a result of the landscape works.

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

3.7 Generic tree protection measures

- i. No fires shall be lit within root protection areas, or under the canopy, of any retained tree on or adjacent to the site.
- ii. No materials should be stored within root protection areas.
- iii. Levels within root protection areas must remain unaltered.
- iv. Contamination or compaction of areas proposed for future landscaping works should be avoided or made good prior to any planting.
- v. Contractor parking or other facilities will not be within root protection areas.
- vi. Herbicides must not be used within root protection areas.
- vii. Excavations and ground vegetation stripping, excluding the removal of trees and shrubs shown for removal, should not be undertaken until root protection areas have been established.
- viii. Retained trees will not be used for the anchorage of equipment or signage.
- ix. Protective fencing should not be moved other than in accordance with this document.
- x. Should incursion into the root protection areas be unavoidable then specific consent from the Local Authority will be needed.
- xi. Unless Planning Consent is granted pruning or removal of any tree should not be undertaken without prior checks with the Local Authority.
- xii. Washing of vehicles with detergents should not be carried out within 5m of root protection areas.
- xiii. Refuelling of vehicles and equipment should not be carried out within 5m of root protection areas.
- xiv. Working with machinery within 5m of the tree canopies should include a banksman.

3.8 Notes for the use of working corridors

- i. Working corridors within root protection areas must have ground protection installed before use.
- ii. Ground protection is to follow the construction detail in Appendix 6 and should only be deviated from with the prior consent of the Local planning Authority.
- iii. The footway will be maintained and kept fit for purpose for the lifetime of its use.
- iv. Waste cement should be cleared off the walkway regularly and removed. It should not be washed off into the root protection areas of trees.
- v. Any pruning required for the installation of working corridors should be carried out by a qualified arborist.

Statement

It is my opinion that provided the recommendations in this report are followed, the proposed development will not have a negative impact on the trees to be retained.

Signed H.

Matt Bardsley MICFor

Dated 27/09/2024

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk Web:www.greenspacetrees.co.uk

Penmaen Isa

Appendix 1 - Definitions / glossary of terms

Adaptive growth an increase in wood in localised areas

suppression of one species by another due to chemical release Allelopophy

Armour Bundled Cable power line usually to a domestic dwelling

Basal sweep stem which curves upwards from the base but then corrects itslef

Bifurcation union producing two stems

Bulge pronounced bulge in a tree's stem or limbs indicating possible

internal issues such as decay

Callus tissue introduced because of a wound, specialising over time to

form a natural repair

Cambium narrow band of cells responsible for the growth of a tree's

circumference

Canker area of damaged bark/cambium normally associated with bacterial

organisms

hole within the tree Cavity

Chlorotic normally associated with the yellowing of leaves

Co-dominant two stems both approximately the same age growing from the

same root stock

Compartmentilisation natural repair of a trees wound

compaction of ground around a tree's root area preventing Compaction

gaseous exchange

Compression Union tight fork between two stems, often considered as a potential

defect

Conservation Area in accordance with the Town & Country Planning Act protects all

trees over 75mm DBH

Crown head of foliage

DBH

Crown lift remove or prune lower branches to raise the trees foliage

Crown reduction reducing a trees overall canopy size

typically associated with branches and limbs Deadwood

Diameter at Breast Height Decay degradation of woody tissues **Deciduous** tree that sheds its leave annually Decline a tree or tree component which is dying Dieback branch tips showing signs of poor health **Dormant** seasonally inactive tree or tree part

End weight uneven distribution of foliage favouring the branch terminuses **Epicormic growth** shoots formed when dormant bud growth is triggered often

through stress

Etiolated reaching for light, generally resulting in a tall, unbalanced, or

slender tree

Extension growth growth put on the previous growing season suggesting vitality

Exudation weeping, oozing

Fibrous roots also root fibres absorbing roots normally within top 30cm of soil

Formative pruning a tree to shape usually started at young age

Cally - Carlo

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans **Planting Plans • House Buyer Reports**

Penmaen Isa Penmaenmawr Conwv 1134 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk

Fruiting body Visible part of fungi associated with tree decays

Hazard Beam partially split of branch or limb

central core of the tree Heartwood

Heave / root heave partial movement of a tree's root plate Hung up branch snapped branch suspended above the ground

Hymenoscyphus fraxineus commonly known as Ash Die Back – a disease that affects Fraxinus

species

Included bark/inclusion example; stem or branch growing into one another

Lateral branch growing horizontally from the stem Live crown ration percentage of live crown able to photosynthesis

Monolith trunk with crown removed, usually kept for ecological value

Multi-stemmed having more than two stems

Natural bracing where branches intertwin to support one another **Pioneer species** first species to populate an abandoned site

Primary union first point from the ground where a trunk develops into stems or

branches

Pollard process of removing branches from a tree to promote epicormics

growth

Reaction Wood secondary wood developed in response to stress such as a lean **Retrenchment Pruning** pruning method intended to emulate a trees natural aging process

Roots underground tree component responsible for stability and

water/nutrient uptake

Root plate area around the base of the tree where the anchorage roots are

formed

Root pruning sympathetic pruning of roots

Scion part of the tree that is grafted to a root stock

abbreviation of species and species' Sp./Spp.

Supressed affected by a neighbouring tree or obstruction

Stub see 'Topping' Sweep see 'Basal sweep'

Tag/Tree Tag small metal numbered disk attached the tree for identification **Topping** where a limb, branch or stem has been cut with little regard for its

ability to compartmentalise and recover. Contrary to the British

Standard

TPO/Tree Preservation tree protected in accordance with the Town & Country Planning

Order

Vertical shoot normally a reaction to pruning where regrowth extends vertically

rather than horizontally

Waterlogging standing water unable to drain freely normally associated with

compaction

Windthrow, windblown where a tree is blown over

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans **Planting Plans • House Buyer Reports**

Penmaen Isa Penmaenmawr Conwv 1134 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk

Greenspaces Tree & Landscape Consultancy Services Appendix 2 – Tree Survey Data Sheets

Tree No.	Species	*Age Class	Hei	Cr	own (l	Spre VI)			First	Ph)	C လ	C Z	Comments	င	Recomm	endations	71	Radiu			
			eight (M)	N	E	S	A	D.B.H (MM)	st Branch (M)	Physiological Condition	Structural Condition	Est. Remaining Contribution		ategory*			RPA (M²)	us of circle (M)			
7746	Cypress	EM	14	4	4	5	5	260 140 200 200	2E	Poor	Good	<10	In decline with significant crown die back, north crown spread and 2x 200mm stems estimated	D	Not considered to be a constraint to development		4.9	75.6			
7747	Hand kerchief tree	SM	8	2	4	4	3	330	2W	Fair	Fair	20>	Cavity forming around likely decay point at 1.5 above ground level east side	С		Remove to facilitate development		49.3			
7748	Cherry	IMM	5	1	1	1	1	120	15	Poor	Fair	<10	Newly planted tree still needing support, in decline	U	Not considered to be a constraint to development		1.44	6.5			
7749	Cherry	IMM	5	1	1	1	1	110	2W	Poor	Fair	<10	Newly planted tree still needing support, in decline	U	Not considered to be a constraint to development		1.32	5.5			
	*Category	A – High Quali	ty Life of	40yrs	+			te Quality 20	yrs+	C - Low Qua			Poor Quality <10yrs *Sub-Category	1 Arl	ooricultural	2 Landscape	Landscape 3 Cultural				
	*Age Class	Y Young				IMN	1 Immat	ture			SM S	Semi-mature	EM Early mature			M Mature	Mature				

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports Penmaen Isa Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk

Charles Ann Alliga

Tree	Species	*Age Class	I	Cr		Spre (I)	ad		First	Phy	C &	C _R	Comments		Recomm	nendations		Radius (I
No.			Height (M)	N	E	S	W	D.B.H (MM)	Branch (M)	Physiological Condition	Structural Condition	Est. Remaining Contribution		Category*			RPA (M²)	of circle M)
7750	Cherry	IMM	9	2	2	2	2	100 80 80 110 70 60	N/A	Good	Good	10 >	Small group of cherry either growing from the same root stock or planted as a bundle	С	Retain a	nd protect	4.9	20.3
7751	Cherry	IMM	9	2	2	2	2	105 125 120 80 70	N/A	Good	Good	10>	Small group of cherry either growing from the same root stock or planted as a bundle	С	Retain a	Retain and protect		23.7
7752	Sycamore	IMM	6	2	2	1	1	110	1W	Good	Fair	<10	squirrel damaged throughout	U	Not considered to be a constraint to development		1.32	5.5
7753												No tree						
										- Poor Quality <10yrs *Sub-Categor	y 1 Ar	boricultural	2 Landscape	3 C	ultural			
	*Age Class Y Young						ımmaı	ture			SIVIS	SM Semi-mature EM Early mature				M Mature		

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

The state of the s

Tree No.	Species	*Age Class	_	Cr		Spre VI)	ead		23	P	- 42	Ω _T	Comments		Recomm	endations		Rac
NO.		Ciass	Height (M)	N	E	S	W	D.B.H (MM)	First Branch (M)	Physiological Condition	Structural Condition	Est. Remaining Contribution		Category*			RPA (M²)	Radius of circle (M)
7754	Sycamore	IMM	6	1	0	0	3	155	3N	Good	Poor	<10	Badly squirrel damaged throughout	U	a cons	dered to be traint to opment	1.86	10.9
7755	Sycamore	SM	13	4	5	4	5	370	2W	Good	Poor	<10	Badly squirrel damaged historically, top lost and regrown with multiple leaders, vertical cavity at 4m above ground level east side, east crown spread estimated	U	a cons	dered to be traint to opment	4.44	61.9
7756	Elm	SM	14	1	1	1	1	400	N/A	Poor	Poor	<10	Dead elm tree in hedge, diameter estimated	U	a cons	dered to be traint to opment	4.8	72.4
7757	Mixed	SM	7	1	1	1	1	200 Av.	N/A	Poor	Poor	<10	Group of 3 x dying elm trees and 1 x badly squirrel damaged sycamore	U	Not considered to be a constraint to development		2.4	18.1
7760	Sycamore	EM	15	2	2	3	3	640	12N	Good	Good	20>	Slight lean west with high crown form	В	Retain and protect		7.68	185.3
7761	Sycamore	EM	17	4	1	3	3	375 320	3W	Good	Good	20>	Co-dominant as of ground level	В	Retain and protect		5.9	109.9
	*Category	A – High Quality Life of 40yrs+				B - Moderate Quality 20yrs+				rs+ C - Low Quality 10yrs+ U –			Poor Quality <10yrs *Sub-Category 1 Arboricultural 2 Landscape			2 Landscape	3 (Cultural
	*Age Class					IMM Immature				SM Semi-mature						M Mature		

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

The state of the s

Tree No.	Species	*Age Class	т	Cro	Crown Spread (M)			<u> </u>	Ph	0.00	C R	Comments		Recomm	endations		Rad	
			Height (M)	N	È	S	W	D.B.H (MM)	First Branch (M)	Physiological Condition	Structural Condition	Est. Remaining Contribution		Category*			RPA (M²)	Radius of circle (M)
7762	Sycamore	M	24	10	5	7	5	1290	3W	Good	Good	40>	Co-dominant as of 1m above ground level, measured low in accordance with annex C BS5837	Α	Retain a	nd protect	15.48	752.8*
7763	Sycamore	EM	22	2	4	4	2	600	1E	Good	Fair	20>	secondary stem lost at 1m east side	В	Retain a	nd protect	7.2	162.9
7764	Beech	EM	22	3	4	5	5	480	2N	Good	Good	40>	None	Α	Retain a	nd protect	5.76	104.2
7765	Beech	EM	20	5	2	4	5	600	8N	Good	Fair	20>	Co-dominant as of 5m above ground level with reaction wood forming	В	Retain a	nd protect	7.2	162.9
7766	Spruce	IMM	6	2	2	2	2	145	GL	Good	Good	40>	Category C due to size	С	a cons	dered to be traint to opment	1.74	9.5
7767	Willow	SM	5	2	3	2	2	210	1N	Good	Good	10>	Basal flare corrects at 0.5m	С	a cons	dered to be traint to opment	2.52	20
7768	Sycamore	M	18	6	5	3	3	660	2S	Good	Good	40>	Co-dominant as of 4m above ground level	Α	Retain a	nd protect	7.92	197.1
	*Category	tegory A – High Quality Life of 40yrs+ B - Moderate			te Quality 2	20yrs+	C - Low Qua	ality 10yrs+	· U·	Poor Quality <10yrs *Sub-Category 1 Arboricultural			2 Landscape	2 Landscape 3 Cultural				
	*Age Class					IMM	Imma	ture		SM Semi-mature			EM Early mature					

*Capped at 707m² in accordance with BS5837:2012 para. 4.6, sub-para. 4.6.1

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports Penmaen Isa Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk

Tree No.	Species	*Age Class	_	Crown Spread (M)				-	Fi	Ph	0.00	Ω ZI	Comments		Recomm	endations		Radius (I	
1101		Class	Height (M)	N	E		W	D.B.H (MM)	First Branch (M)	Physiological Condition	Structural Condition	Est. Remaining Contribution		Category*			RPA (M²)	of circle M)	
7769	Sycamore	IMM	6	1	1	1	1	160	1W	Fair	Poor	<10	Badly squirrel damaged throughout	U	a const	lered to be raint to pment	1.92	11.6	
7770												No tre	e						
7771	Yew	SM	5	1	2	1	1	160 170 180	1N	Good	Good	20>	Root bound in concrete bed	В		o facilitate opment	3.5	39.3	
7772	Sycamore	SM	10	2	2	3	2	300 380	2W	Good	Good	10 >	Co-dominant as of ground level with inclusion forming	С		o facilitate opment	5.8	106	
7773	Cherry	SM	3	4	0	0	0	140 110	1N	Good	Poor	<10	Historically collapsed but still growing	U	a const	dered to be raint to opment	2.1	14.3	
7774	Western red cedar	SM	10	4	4	4	4	300 360 160 285 305	2N	Good	Good	10>	Ornamental, multi stemmed tree, lever arm forming at west side	С	Remove to facilitate development		7.8	189.8	
7775	White beam	EM	7	2	3	1	1	280	3N	Fair	Poor	<10	Decay at primary union and base, tree biased west	U	Not considered to be a constraint to development		3.36	35.5	
	*Category A – High Quality Life of 40yrs+ B - Moderate O							<u> </u>				Poor Quality <10yrs *Sub-Category	<u> </u>			ultural			
	*Age Class Y Young						IMM Immature				SM S	emi-mature	EM Early mature M			M Mature	Mature		

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

_	•	4.4				_												
Tree No.	Species	*Age Class	۱ ـ	Cro	wn (N	Spre	ead		27	P	0.00	$\Omega_{\rm T}$	Comments		Recomm	endations		Rac
NO.		Olass	Height (M)	N	E	S	W	D.B.H (MM)	First Branch (M)	Physiological Condition	Structural Condition	Est. Remaining Contribution		Category*			RPA (M²)	Radius of circle (M)
7776	Beech	SM	9	2	4	2	2	325	2E	Good	Good	20>	Poorly pruned historically	В		o facilitate opment	3.9	47.8
7777	Sycamore	SM	8	1	2	2	2	170 140	2S	Good	Fair	<10	Co-dominant as of ground level with significant inclusion	U	a cons	dered to be traint to opment	2.6	21.9
7778	Laburnum	SEM	5	1	1	1	1	80 80 70	GL	Good	Fair	<10	Collapsed historically and regrowing	U	a cons	dered to be traint to opment	1.6	8
7779	Laburnum	EM	4	1	1	1	1	180 120	1W	Good	Fair	<10	Significant inclusions associated with species	U	a cons	dered to be traint to opment	2.6	21.2
7780	Beech	SM	5	2	3	2	1	325	15	Good	Good	10>	Multple pruning points throughout primary union	С		o facilitate opment	3.9	47.8
7781												No tre	e					
7782	White beam	EM	6	3	4	1	0	190 220	1E	Good	Fair	10>	Whole tree biased east	С		o facilitate opment	3.5	38.2
7783	Magnolia	EM	5	3	3	2	1	105 105	GL	Good	Good	10>	Category C due to size	С		o facilitate opment	1.8	10
	*Category	A – High Qual	ity Life o	f 40yrs+		B - N	B - Moderate Quality 20yrs+ C				ality 10yrs+	+ U	Poor Quality <10yrs *Sub-Category	1 Arboricultural 2 Landscape			3 (Cultural
*Age Class Y Young						IMM	Imma	ture		SM Semi-mature			EM Early mature	M Mature				

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Troc	Chaoise	*^~		Crown Spread									Comments		Decerem	nendations		_
Tree No.	Species	*Age Class	He	N	WN (N	<u>(۱)</u>	w		First	Phys Co	Str	Rei	Comments	Ca	Recomin	iendations	꾸	Radius (I
			Height (M)	N	_	0	VV	D.B.H (MM)	t Branch (M)	Physiological Condition	Structural Condition	Est. Remaining Contribution		Category*			RPA (M²)	Is of circle (M)
7784	Willow	IMM	4	1	1	1	1	80	1W	Good	Good	10>	Category C due to size	С		to facilitate opment	0.96	2.9
7785	Apple	EM	3	1	1	1	1	225	GL	Good	Fair	10>	Heavily pruned historically and regularly pruned for the production of fruit	С		to facilitate opment	2.7	22.9
7787	Western red cedar	EM	14	2	2	2	2	410 180 280	2N	Good	Fair	20>	Central stems removed historically, planted as part of a linear group	В		to facilitate opment	6.3	126.2
7788	Western red cedar	EM	14	2	2	1	2	315	3N	Good	Good	20 >	Planted as part of a linear group	В		to facilitate opment	3.78	44.9
7789	Western red cedar	EM	14	3	3	1	2	210 325 350 225	3N	Good	Fair	20>	Central stems removed historically, planted as part of a linear group	В		to facilitate opment	6.8	146.1
7790	Lawson cypress	EM	12	3	3	2	2	330 245	3N	Poor	Good	<10	Sparse crown suggesting tree is in decline	U		to facilitate opment	4.9	76.4
7791	Willow	EM	6	10	9	0	7	480	2S	Good	Poor	<10	Crown heavily biased north to the point of needing support	U	devel	to facilitate opment	5.76	104.2
	*Category	•							C - Low Quality 10yrs+ U - SM Semi-mature			- Poor Quality <10yrs *Sub-Category	1 Ark	ooricultural	2 Landscape	3 C	Cultural	
	"Age Class	*Age Class Y Young				IMM Immature					SIVIS	emi-mature	EM Early mature			M Mature		

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Caroling Brown () 119

Tree No.	Species	*Age Class	_	Cro		Spre /I)	ead		Ę	Phy.	0.00	ς ₂₂	Con	nments	ဂ	Recomm	endations	_	Rad
		Ciass	Height (M)	N	E	S	W	D.B.H (MM)	rst Branch (M)	ysiological Condition	Structural Condition	Est. Remaining Contribution			category*			RPA (M²)	dius of circle (M)
7792	Cherry	EM	4	2	2	2	2	225	1N	Good	Good	10>	Small orna	mental cherry	С	C Remove to facilitate development		2.7	22.9
7793	Cherry group	SM	11	3	1	3	3	225 av.	N/A	Good	Good	20>	linear group of	600, smallest 150, f 7x stems, heavily st side for utilities	В		o facilitate opment	2.7	22.9
7794	Lawson cypress	SM	3	0	1	1	1	145	3	Good	Poor	<10		rically leaving 3m cump	U		o facilitate opment	1.74	9.5
H1	Cypress Hedge	SM	5	1	1	1	1	150 Av.	G/L	Good	Good	20>	Cypress bo	undary hedge	В	B Cut to shape and retain and protect		1.8	10.2
	*Category *Age Class	A – High Quali Y Young	ty Life of	40yrs+			1odera I Imma	te Quality 2 ture	20yrs+	C - Low Qua		emi-mature	– Poor Quality <10yrs	*Sub-Category EM Early mature	1 Art	1 Arboricultural 2 Landscape M Mature		3 (Cultural

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Greenspaces Tree & Landscape Consultancy Services Appendix 3 – BS5837:2012 Cascade Chart for tree categorisation

BS5837:2012 Table 1 - Cascade chart for tree quality assessment

Caroling Brown Collins

Category and definition	Criteria (including subcategories where appropriate	9)		Identification on plan							
Trees unsuitable for retention (see Not	e)										
Category U Those in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years											
97	1 Mainly arboricultural qualities	2 Mainly landscape qualities	3 Mainly cultural values, including conservation								
Trees to be considered for retention											
Category A Trees of high quality with an estimated remaining life expectancy of at least 40 years	Trees that are particularly good examples of their species, especially if rare or unusual; or those that are essential components of groups or formal or semi-formal arboricultural features (e.g. the dominant and/or principal trees within an avenue)	Trees, groups or woodlands of particular visual importance as arboricultural and/or landscape features	Trees, groups or woodlands of significant conservation, historical, commemorative or other value (e.g. veteran trees or wood-pasture)								
Category B Trees of moderate quality with an estimated remaining life expectancy of at least 20 years	Trees that might be included in category A, but are downgraded because of impaired condition (e.g. presence of significant though remediable defects, including unsympathetic past management and storm damage), such that they are unlikely to be suitable for retention for beyond 40 years; or trees lacking the special quality necessary to merit the category A designation	Trees present in numbers, usually growing as groups or woodlands, such that they attract a higher collective rating than they might as individuals; or trees occurring as collectives but situated so as to make little visual contribution to the wider locality	cultural value								
Category C Trees of low quality with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150 mm	Unremarkable trees of very limited merit or such impaired condition that they do not qualify in higher categories	Trees present in groups or woodlands, but without this conferring on them significantly greater collective landscape value; and/or trees offering low or only temporary/transient landscape benefits	Trees with no material conservation or other cultural value								

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Penmaen Isa Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931

Email:admin@greenspacetrees.co.uk Web:www.greenspacetrees.co.uk

Greenspaces Tree & Landscape Consultancy Services Appendix 4 – Protective Fencing Design Examples

BRITISH STANDARD BS 5837:2012

Graffly - 12 to your () 19 1

Figure 3 Examples of above-ground stabilizing systems





Figure 2 Default specification for protective barrier



Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Greenspaces Tree & Landscape Consultancy Services Appendix 4 continued – Heras Steadfast System

Caroling Zang William



Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Greenspaces Tree & Landscape Consultancy Services Appendix 5 – RPA Example Sign 1



Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Greenspaces Tree & Landscape Consultancy Services Appendix 5 continued – RPA Example Sign 2


Craffy - Day - A A A A A



Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Greenspaces Tree & Landscape Consultancy Services Appendix 6 – Working Corridor - Scaffolding or light foot traffic within the RPA

- P. Carrie - Property - A. A. A. A.



Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

College College

Plans

Appendix 7 – Vegetation Location Plan

Appendix 8 - Tree Location Plan

Appendix 9 – Tree Constraints Plan


Appendix 10 – Tree Protection Plan

The Tree Location, Constraints and Protection Plans should be submitted with your application as separate PDF.'s for on-site use by the Local Planning Authority


Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports Penmaen Isa Penmaenmawr Conwy LL34 6NS Tel: 01492 623703

Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk Web:www.greenspacetrees.co.uk


Parally - Dear Willy



- Charley - Dear - Children



Garafila - Dana () 194



Garafila - Dana () 194



Appendix 11 – Images



7746 - tree at entrance to site clearly in decline



7747 – ornamental tree (Handkerchief tree) typical for the garden area



Cavity forming tree 7747

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports



7748 & 7749 – recently planted cherry trees (tree on right too small, <75mm to be included in survey)



7769 – typical small ornamental proposed for removal




7774 – ornamental garden tree proposed for removal

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

File Continue of the Continue







Co-dominant stems with inclusions forming to tree 7777



Laburnum 7778 – poor form and inclusions

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports



Parally - Marin Alliga

7790 – showing a sparse crown associated with decline




77981 – willow in need of support in order to stay upright



Typical shrub bed on the site

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports



The state of the s

Tree 7790 with trees 7787 – 7789 behind, all proposed for removal



Ornamental trees along the west boundary



View from the garden looking north towards the woodland to be retained

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Credentials of the arboriculturist

This report was prepared by Matt Bardsley who holds the following qualifications and accreditations: -

Chartered Arboriculturalist with Institute of Chartered Foresters

Professional member of the Arboricultural Association (PR5720)

HND Arboriculture & Woodland Management

Royal Forestry Society Certificate in Arboriculture

Lantra Professional Tree Inspection Qualification

Lantra Instructor Qualification



Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports

Penmaen Isa Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk

Ed Crista and Allies

Bibliography

A Guide to Good Practice: the use of cellular confinement systems close to trees, The Arboricultural Association

A-Z of tree terms; A Companion to British Arboriculture, Philip Wilson

BS3998:2010 Recommendations for Tree Work, British Standards Institute

BS5837:2012 Trees in relation to design, demolition and construction – recommendations. British Standards Institute

Geo-tech Tree Root Protection System, geo-tech.co.uk

Hilliers Manual of Trees and Shrubs, 3rd Edition, Thomas Hillier & Son

Landis, Landis.org.uk

The consultants guide to writing effective reports, The American Society of Consulting Arborists

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports Penmaen Isa Penmaenmawr Conwy LL34 6NS Tel: 01492 623703

Mobile: 07845 928931 Email:admin@greenspacetrees.co.uk Web:www.greenspacetrees.co.uk

Garage Comments

End of Document (Intentionally blank)

Tree Hazard Inspections • BS5837 Trees on Development Reports • Planning Advice Tree Preservation Order Applications • Tree & Woodland Management Plans Planting Plans • House Buyer Reports Penmaen Isa Penmaenmawr Conwy LL34 6NS Tel: 01492 623703 Mobile: 07845 928931

Email:admin@greenspacetrees.co.uk Web:www.greenspacetrees.co.uk